


MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY  
Office of Land and Water Resources  
P. O. Box 2309  
Jackson, MS 39225  
Water Well Plugging/Decommissioning Form  
OLWR-DF-1 (04/08)  
(601)961-5555 (601)961-5228 (fax)

COUNTY WELL LOCATED: Leflore	WELL NUMBER: 1 <b>L87</b>
PERMIT NUMBER: MS GW-03988	DATE WELL PLUGGED: 03/30/2021
NAME OF FIRM PLUGGING WELL: Mid South Water, LLC	TELEPHONE NUMBER: (662) 843-4076
NAME AND ADDRESS OF CURRENT LANDOWNER: Greenwood Utilities Commission P.O. Box 866, Greenwood, MS 38935	
WELL LOCATION: SECTION: TOWNSHIP: RANGE:	
WELL LOCATION: LATITUDE: 33°31'6.8"	LONGITUDE: 90°12'37.2"
METHOD (Check ONE): <input type="checkbox"/> USGS QUAD <input type="checkbox"/> CONVENTIONAL SURVEY <input checked="" type="checkbox"/> GPS - HAND HELD OR SURVEY GRADE	
DISTANCE: DIRECTION: NEAREST TOWN: OTHER LANDMARK: Henderson Plant	
WELL PURPOSE (HOME, IRRIGATION, MUNICIPAL, ETC.): Power generation	
NAME OF WELL CONTRACTOR WHO DRILLED THE WELL: Layne	
NAME OF LANDOWNER WHEN WELL WAS DRILLED: Greenwood Utilities Commission	

WELL DATA			
WELL DEPTH: 100'	HOLE DEPTH:		
CASING DIAMETER (IN.): 26"	CASING LENGTH (FT.):	TYPE OF CASING: steel	
DEPTH TO STATIC WATER LEVEL: 30'	DATE WELL COMPLETED: 1960		
WHY IS THE WELL BEING ABANDONED? No longer in use			

DESCRIBE HOW THE WELL OR HOLE WAS PLUGGED (AMOUNT OF CASING AND/OR SCREEN THAT WAS REMOVED OR LEFT IN HOLE, MATERIAL AND AMOUNT USED IN PLUGGING, METHOD OF PLACING MATERIAL, ETC.)
- Pulled pumping equipment from well
- Installed 2" pipe to 90'
- Pumped 14 yd <sup>3</sup> of neat cement into the well through the 2" pipe
- Obtained cement returns at ground level
- Removed concrete foundation
- Cut the casing off 4' below ground surface
- Dressed the site

I CERTIFY THAT THE WELL WAS PLUGGED OR ABANDONED IN ACCORDANCE WITH THE STATE OF MISSISSIPPI REGULATIONS.	
Clayton Miller	0-703
PRINT NAME	MS LICENSE NUMBER
	03/31/2021
SIGNATURE	DATE

RECEIVED  
APR 05 2021  
BY OLWR