

Leflore
L156
9-13-63

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

CODED

Date: 9-13-1963, Driller: Layne-Central Co. County Leflore
(Name)

(1) Owner of Land: Greenwood Utilities
(Name)
Greenwood, Mississippi
(Address)

(2) Location: NE 1/4, NW 1/4, Sec. 15 T 19 N R 1 E
_____ miles _____ of _____
(distance) (direction) (Nearest Town)

(3) Topography: _____
(Hilly) (Flat) (Level)

(4) Purpose of Well: Municipal
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
gumbo	18	18
sand & clay streaks	16	34
coarse sand & pea grav.	59	93
hard blue clay	32	125
white sand & clay balls	25	150
loose sand	85	235
coarse sand	23	258
hard clay	34	292

Information upon completion of well:

(1) Diameter 16 inches.

(2) Total Depth 252 feet.

(3) Water Level 62 feet below top of ground.

(4) Cased to 122', Size 16"

(5) Screen: Size 12", Length 77'


(6) Were any formations sealed against pollution?
x yes, _____ no.

If YES depth of formation 122'

Why _____ required.

Drillers Remarks: _____

CODED



(Use Back Side)

Well No.

Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200