

L 160

WATER WELL DRILLERS LOG

10-66 E Log 68

Date: OCT 15, 1966, Driller: DELTA DRILLING Co County LEFLORE

(Name)

(1) Owner of Land: DAVID M. NERO (Name)

RT. 1, GREENWOOD, MISS (Address)

(2) Location: SW 1/4, NE 1/4, Sec. 24 T4R15E

5 miles SE of GREENWOOD (distance) (direction) (Nearest Town)

(3) Topography: FLAT (Hilly) (Flat) (Level)

(4) Purpose of Well: DOMESTIC (Domestic Irrigation) (Municipal, Industrial, Other)

| Description & Color of Materials Sand, Clay, Red Clay, Shell, etc. | Thick- ness Feet | Depth Feet |
|---|------------------------|---------------|
| gumbo | 39 | 39 |
| Sand | 40 | 79 |
| gravel | 25 | 104 |
| Sand | 24 | 129 |
| gumbo | 26 | 155 |
| Shale | 29 | 184 |
| gumbo | 29 | 213 |
| green shale | 42 | 255 |
| Sand | 49 | 304 |
| Shale | 24 | 328 |
| green sand | 35 | 363 |
| green shale | 54 | 417 |
| greensand | 26 | 443 |
| gumbo | 26 | 469 |
| Shale | 52 | 521 |
| green sand | 39 | 560 |
| Shale | 17 | 577 |
| Sand | 14 | 591 |
| green shale | 9 | 600 |
| Sand | 77 | 677 |
| Shale | 23 | 710 |

Information upon completion of well:

(1) Diameter 4.3 inches.

(2) Total Depth 710 feet.

(3) Water Level FLOWS feet below top of ground.

(4) Cased to 682' , Size 2" 262' 104'

(5) Screen: Size 2" , Length 20

(6) Were any formations sealed against pollution?

yes, no. 679 20

If YES depth of formation 442


Why

Drillers Remarks: 25' LAP OF 2" IN 3"

PIPE - FLOWS 20 gpm - 21'

2" TAIL PIPE ON BOTTOM

END OF WELL



(Use Back Side)

Well No.

