

Leflore

MISSISSIPPI BOARD OF WATER COMMISSIONERS

M-1

WATER WELL DRILLERS LOG

**CODED**

1-7-63

Date: JAN 7, 1963, Driller: DELTA DRILLING Co. County LEFLORE

(Name)

(1) Owner of Land: TRAVIS H. CLARK  
(Name)

MORGAN CITY, MISS  
(Address)

(2) Location: 1/4, NW 1/4, Sec. 21 T18R2W

           miles           , of             
(distance) (direction) (Nearest Town)

(3) Topography:             
(Hilly) (Flat) (Level)

(4) Purpose of Well: DOMESTIC  
(Domestic Irrigation  
Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter 3 inches.

(2) Total Depth 1338 feet.

(3) Water Level WELL FLOWS feet below top of ground.

(4) Cased to 1318, Size 706' 3" / 62.5' 2"

(5) Screen: Size 2", Length 20'  
27'-LAP OF 2" IN 3" PIPE

(6) Were any formations sealed against pollution?  
           yes,            no.


If YES depth of formation           

Why           

Drillers Remarks:           

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
SAND	84	84
GRAVEL	63	147
GUMBO	32	179
SAND	23	202
GUMBO	12	214
SAND	41	255
GUMBO	72	277
SAND	31	308
GUMBO	20	328
SAND	84	412
GUMBO	14	426
SHALE	38	464
SAND	166	630
GUMBO W/ROCKS-	74	704
SHALE W/ROCKS-	32	736
SAND W/ROCK @ 790'	178	914
SHALE	44	958
GUMBO	40	998
SHALE W/ROCKS-	48	1048
SAND W/ROCKS-	52	1100
SHALE	20	1120
GUMBO	14	1134
SAND	32	1166
GUMBO	52	1218
SHALE	20	1238
SAND	43	1281
GUMBO	9	1290
WHITE SAND	48	1338

**CODED**



Well No.

1913

1913