


Leflore
N 8
3-16-62

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG
CODED

Date: MAR 16, 1962, Driller: DELTA DRILLING Co. County: LEFLORE
(Name)

		Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>MACK KIMBROUGH</u> (Name)		<u>SANDY LOAM</u>	<u>61</u>	<u>61</u>
<u>MORGAN CITY, MISS</u> (Address)		<u>GRAVEL</u>	<u>84</u>	<u>145</u>
(2) Location: <u>NW 1/4, SW 1/4, Sec. 27 T8N R1W</u>		<u>SAND</u>	<u>15</u>	<u>160</u>
<u>3 1/2</u> miles <u>NE</u> , of <u>MORGAN CITY</u> (distance) (direction) (Nearest Town)		<u>GUMBO</u>	<u>18</u>	<u>178</u>
(3) Topography: _____ (Hilly) (Flat) (Level)		<u>SAND</u>	<u>312</u>	<u>490</u>
(4) Purpose of Well: <u>DOMESTIC</u> (Domestic Irrigation Municipal, Industrial, Other)		<u>GUMBO CODED ROCK</u>	<u>113</u>	<u>603</u>
		<u>SAND W/6" ROCK</u>	<u>10</u>	<u>613</u>
		<u>GUMBO W/ 7" ROCK</u>	<u>15</u>	<u>628</u>
		<u>SHALE</u>	<u>26</u>	<u>654</u>
		<u>SAND</u>	<u>23</u>	<u>677</u>
		<u>SHALE W/10" ROCK</u>	<u>59</u>	<u>736</u>
		<u>GUMBO W/HARD ROCKS</u>	<u>32</u>	<u>768</u>
		<u>SAND</u>	<u>28</u>	<u>796</u>
		<u>GUMBO</u>	<u>27</u>	<u>823</u>
		<u>SAND W/6" ROCK -</u>	<u>72</u>	<u>895</u>
		<u>GUMBO W/5" ROCK.</u>	<u>12</u>	<u>907</u>
		<u>SAND</u>	<u>127</u>	<u>1034</u>
		<u>GUMBO</u>	<u>10</u>	<u>1044</u>
		<u>SAND</u>	<u>40</u>	<u>1084</u>
		<u>SHALE</u>	<u>11</u>	<u>1095</u>
		<u>SAND</u>	<u>80</u>	<u>1175</u>
Information upon completion of well:				
(1) Diameter <u>3</u> inches.				
(2) Total Depth <u>1175</u> feet.				
(3) Water Level <u>WELL FLOW</u> feet below top of ground.				
(4) Cased to <u>1175</u> , Size <u>3x2"</u>				
(5) Screen: Size <u>2</u> , Length <u>30'</u>				
(6) Were any formations sealed against pollution? _____yes, _____no.				
If YES depth of formation _____				
Why _____				
Drillers Remarks: <u>15' LAP OF 2" IN</u> <u>3" PIPE</u>				



(Use Back Side)

Well No.

