


N 9

4-14-62

WATER WELL DRILLERS LOG CODED

Date: APRIL 14, 1962, Driller: DELTA DRILLING Co. County LEFLORE
(Name)

		Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>JOHN E. LINDSEY</u> (Name)		<u>GUMBO</u>	<u>32</u>	<u>32</u>
<u>SIDON, MISS.</u> (Address)		<u>SAND</u>	<u>28</u>	<u>60</u>
(2) Location: <u>SE 1/4, SW 1/4, Sec. 12 T18N R1W</u>		<u>GRAVEL</u>	<u>75</u>	<u>135</u>
<u> </u> miles <u> </u> , of <u> </u> (distance) (direction) (Nearest Town)		<u>SAND</u>	<u>103</u>	<u>238</u>
(3) Topography: <u>DELTA</u> (Hilly) (Flat) (Level)		<u>GUMBO</u>	<u>33</u>	<u>271</u>
(4) Purpose of Well: <u>DOMESTIC</u> (Domestic Irrigation Municipal, Industrial, Other)		<u>SAND CODED</u>	<u>122</u>	<u>393</u>
Information upon completion of well:		<u>GUMBO</u>	<u>87</u>	<u>480</u>
(1) Diameter <u>3</u> inches.		<u>SHALE w/3" ROCK</u>	<u>54</u>	<u>534</u>
(2) Total Depth <u>1067</u> feet.		<u>GUMBO</u>	<u>26</u>	<u>560</u>
(3) Water Level <u>WELL FLOWS</u> feet below top of ground.		<u>SAND</u>	<u>18</u>	<u>578</u>
(4) Cased to <u>1067</u> , Size <u>3 x 2"</u>		<u>SHALE</u>	<u>7</u>	<u>585</u>
(5) Screen: Size <u>2"</u> , Length <u>30' SS.</u> <u>.012 GA.</u>		<u>GREEN SAND - w/4" ROCK</u>	<u>20</u>	<u>605</u>
(6) Were any formations sealed against pollution? <u> </u> yes, <input checked="" type="checkbox"/> no.		<u>SHALE w/6" ROCK -</u>	<u>21</u>	<u>626</u>
If YES depth of formation <u> </u>		<u>GREEN SAND</u>	<u>18</u>	<u>644</u>
Why <u> </u>		<u>SHALE</u>	<u>24</u>	<u>668</u>
Drillers Remarks: <u> </u>		<u>SAND -</u>	<u>3</u>	<u>671</u>
		<u>SHALE</u>	<u>22</u>	<u>693</u>
		<u>GUMBO</u>	<u>6</u>	<u>699</u>
		<u>SHALE w/3" ROCK -</u>	<u>30</u>	<u>729</u>
		<u>SAND -</u>	<u>54</u>	<u>783</u>
		<u>SHALE</u>	<u>42</u>	<u>825</u>
		<u>SAND -</u>	<u>62</u>	<u>887</u>
		<u>SHALE</u>	<u>69</u>	<u>956</u>
		<u>WHITE SAND</u>	<u>111</u>	<u>1067</u>



(Use Back Side)

Well No.

