

WATER WELL DRILLERS LOG

**CODED**

Date: Oct. 10, 1960, Driller: DELTA DRILLING Co. County LEFLORE

1534

(Name)

(1) Owner of Land: W. H. LINDSEY

(Name)

SILDON, MISS-

(Address)

(2) Location: 1/4, 1/4, Sec. 4 T17R10

           miles            of             
(distance) (direction) (Nearest Town)

(3) Topography:            (Hilly)            (Flat)            (Level)

(4) Purpose of Well: DOMESTIC  
(Domestic Irrigation  
Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter 3 inches.

(2) Total Depth 1191 feet.

(3) Water Level WELL FLOWS  
6.5 GPM feet below top of ground.

(4) Cased to 1191', Size 2" 483'

(5) Screen: Size 2, Length 30'

(6) Were any formations sealed against pollution?

           yes,            no.

If YES depth of formation           


Why           

Drillers Remarks: 20' LAP OF 2"

PIPE IN 3" PIPE -

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
SAND + GRAVEL	188	188
GUMBO	159	347
SAND	125	472
GUMBO W/SAND STREAKS	52	524
GUMBO W/6" ROCK-	107	631
SHALE W/SANDY STREAKS	67	698
GREEN SAND W/4" ROCK 743	75	773
SHALE	16	789
GREEN SAND W/6" ROCK-	46	835
SAND W/3+4" ROCK 10'+10' APART	73	908
SHALE	16	924
SAND W/6" ROCK-	35	959
SANDY SHALE	12	971
BROWN SAND W/3" ROCK	28	989
GUMBO	29	1018
SHALE	44	1062
FINE SAND	19	1081
WHITE SAND	110	1191

**CODED**



(Use Back Side)

Well No.

1911

1912

1913

1914

1915

1916

1917

1918

1919

1920

1921

1922

1923

1924

1925

1926

1927