

Leflore
 32
 1-30-61

WATER WELL DRILLERS LOG

2
CODED

Date: JAN. 30, 1961, Driller: DELTA DRILLING Co. County: LEFLORE

(Name)

(1) Owner of Land: LUTHER LINDSEY
 (Name)

RTE. 1, BOX 8, SIDON, MISS.
 (Address)

(2) Location: 22 $\frac{1}{4}$, 25 $\frac{1}{4}$, Sec. T18R1W

 miles of
 (distance) (direction) (Nearest Town)

(3) Topography: (Hilly) (Flat) (Level)

(4) Purpose of Well: DOMESTIC
 (Domestic Irrigation
 Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter 3 inches.

(2) Total Depth 1087 feet.

(3) Water Level WELL FLOWS feet below top of ground. 3'-54"

(4) Cased to 1087', Size 2" 526'

(5) Screen: Size 2", Length 30'
10' LAP OF 2" IN 3" PIPE


(6) Were any formations sealed against pollution?
 yes, no.

If YES depth of formation

Why

Drillers Remarks:

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
GUMBO & SAND	64	64
GRAVEL	85	149
GUMBO	61	210
SAND	74	284
GUMBO	60	344
SHALE	12	356
SAND	24	380
SHALE	18	398
SAND	42	440
SHALE	20	460
GUMBO w/6" ROCK 10'		
TO 15' APART	96	556
SAND	14	570
SHALE w/6" ROCK	36	606
SAND w/4" ROCK	55	661
GREEN SAND w/6" ROCK	69	730
SHALE	53	783
GREEN SAND w/6" ROCK	77	860
SHALE	12	872
SAND	44	916
SHALE	55	971
GUMBO	26	997
SHALE	11	1008
WHITE SAND	79	1087



(Use Back Side)

Well No.

0000

1111