

MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY

Office of Land and Water Resources

P. O. Box 10631
Jackson, MS 39289-0631
WATER WELL DRILLERS LOG

COUNTY WELL LOCATED
Lincoln

WELL NUMBER *295*

DATE WELL COMPLETED
1-29-99

GRANT NUMBER
Grant Water Well & Supply

1318 Pricedale Dr. SE

NAME OF DRILLING FIRM
Bogue Chitto

MS 39629

NAME & MAILING ADDRESS OF LANDOWNER
Lisa Stevens

640 Luther Trail

Bogue Chitto

WELL LOCATION: SEC 7 TOWNSHIP 6 RANGE 7

DISTANCE 1 1/2 Miles DIRECTION NE of Best Lincoln

OTHER LANDMARK

WELL PURPOSE: Home, Irrigation, Municipal, Industrial, Fish Pond, etc.

PUMP DATA

PUMP TYPE (Circle One): Submersible, Turbine, Jet, Flowing Well, Other (Describe) _____

POWER TYPE (Circle One): Electric, Tractor, Diesel, Gasoline, Butane, Other (Describe) _____ H/P 1

Pump Capacity (GPM) 16 No. of Stages 10 Setting Depth 77' FT.

PUMP TEST

Well yielded 16 GPM with a drawdown of 0 ft. after 1 hours of pumping

WELL DATA

Well Depth 78' Casing Diameter (In.) 4" Casing Length (Ft.) 68'

Type of Casing PVC Hole Depth 85 Depth to Static Water Level 48'

LOG DATA

TYPE OF LOG RUN (Circle One): No Log Run, Electric, Gamma Ray, Density, Sonic, Neutron, Other (Describe) _____

Name of Organization Running Log

TYPE OF COMPLETION: (Circle One or More): Gravel Packed, Underreamed, Telescoped, Natural Development, Open Hole, Other (Describe) _____

GEOLOGIC DATA (Office Use Only)

Surface Elev.	Geologic Unit	Unit Thickness	Depth to Top
Subs. SWL	Date	Analysis	Aquifer Test

WELL GROUTED TO A DEPTH OF 10 FEET

Type Grout (circle one): Cement, Bentonite, or Mix

Driller's Remarks


Top of Lap Pipe or Reduction in Casing

FEET IF TELESCOPED OR MORE THAN ONE SCREEN: USE BACK PAGE

SCREEN DATA

Diameter - Inches 4" Length - Feet 20' Slot Size - Inches .010

Screen Type PVC Depth to Bottom - Feet 78'

DESCRIPTION OF FORMATIONS ENCOUNTERED	FROM	TO	FORMATIONS (Continued)	FROM	TO
Red Clay	0	25	 JUN 28 1999 Dept. of Environmental Quality Office of Land & Water Resources		
Sand	25	74			
Gravel	74	78			
White Clay	78	85			

IF MORE SPACE IS NEEDED, USE BACK

