

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

CODED

WATER WELL DRILLERS LOG

LOWNDES
A 35
5/31/83

5-31 1983 Clardy Well, Drilling LOWNDES
date well completed firm name county well located

LANDOWNER: Thomson-Monk
2220 Dallas Center
Dallas, Texas 75201
(mailing address)

WELL LOCATION:
sec. 24 T. 16 N. R. 10 E
7 miles NE of West
(distance) (direction) (nearest town)

WELL PURPOSE: industrial
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

(1) diameter (inches) 4"

(2) total depth (feet) 409'

(3) static water level (feet) 120' below above top of ground.

(4) casing PVC 300'
(material) (depth)
4"
(size) if telescope see back.

(5) screen 30'
(length) (depth to top)
2" PVC
(size) (material)

(6) pump 5 3500 gph.
(HP) (yield gpm)
elec
(type power)

(7) electric log no CODED
(yes or no)
(organization running log)

Description of formations encountered	from	to
red Clay	0	23
sand	23	31
sandy blue Clay	31	35
lime rock	35	47
sandy Clay	47	57
rock 2"	57	
sandy Clay	57	105
sand	105	138
sandy Clay	138	141 1/2
rock 2"	148 1/2	
Clay	148 1/2	157
sandy Clay	157	194
fine Clay	194	208
sandy Clay	208	211
small rock	211	
hard Clay	211	230
sand	230	231
sandy Clay	231	237
rock	237	237 1/2
sand	237 1/2	239
hard Clay	239	259
sand	259	263
sandy Clay	263	278
sand	278	280
sandy Clay	280	281
rock 2"	281	
sandy Clay	281	285
hard Clay	285	294
sandy Clay	294	298
sm. rock 2"	298	
sandy Clay	298	304
rock	304	309
heavy Clay	309	316
gummy Clay	316	325
sand	325	332
hard Clay	332	339
rock 12"	339	
sandy Clay	339	343
gummy Clay	343	353
sand	353	358


(8) how well bore DEPT. OF NATURAL RESOURCES BUREAU OF LAND & WATER RESOURCES

DRILLERS REMARKS: JUN 20 1983

RECEIVED

If well telescopes please
sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.