

LOWNDES
G 2115

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

WATER WELL DRILLERS LOG

7/24/86 date well completed
Clardy Well Drilling Lowndes firm name
county well located

LANDOWNER: Ned King

Rt 7 Box 2438

Colo, ms.
(mailing address)

WELL LOCATION:

sec. 6 T-18 N. R-18 E
1/2 miles W of Colo.
(distance) (direction) (nearest town)

WELL PURPOSE: Domestic
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:


- (1) diameter (inches) 4"
- (2) total depth (feet) 162'
- (3) static water level (feet) 12' below top of ground.
- (4) casing PVC 91'
(material) (depth)
4"
(size) if telescope see back.
- (5) screen _____
(length) (depth to top)
(size) (material)
- (6) pump 1/2 900 gph
(HP) (yield gpm)
elec.
(type power)
- (7) electric log no
(yes or no)
(organization running log)
- (8) how well bottom plugged _____

description of formations encountered

from

to

<u>Sand & gravel</u>	<u>9</u>	<u>36</u>
<u>Sandy blue clay</u>	<u>36</u>	<u>46</u>
<u>rock</u>	<u>46</u>	<u>46 1/2</u>
<u>Sandy clay</u>	<u>46 1/2</u>	<u>58</u>
<u>good clay</u>	<u>58</u>	<u>93</u>
<u>Sandy clay</u>	<u>93</u>	<u>108</u>
<u>good clay</u>	<u>108</u>	<u>110</u>
<u>Sandy clay</u>	<u>110</u>	<u>113</u>
<u>rocky</u>	<u>113</u>	<u>118</u>
<u>sand</u>	<u>118</u>	<u>123</u>
<u>blue clay</u>	<u>123</u>	<u>130</u>
<u>rocky</u>	<u>130</u>	<u>134</u>
<u>blue clay</u>	<u>134</u>	<u>145</u>
<u>sand</u>	<u>145</u>	<u>158</u>
<u>blue clay</u>	<u>158</u>	<u>162</u>




SEP 03 1986

Department of Natural Resources
Bureau of Land & Water Resources

DRILLERS REMARKS:

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.