

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

WATER WELL DRILLERS LOG

Louder  
H  
2043

8-30 1983 Clardy Well Drilling Louder  
 date well completed firm name county well located

LANDOWNER: Bruce Myers  
Rt 4  
Celo, ms.  
 (mailing address)

WELL LOCATION:  
 sec. 11 T 18 N R. 17 E  
4 miles E of Celo.  
 (distance) (direction) (nearest town)

WELL PURPOSE:  
 (home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

(1) diameter (inches) 4"

(2) total depth (feet) 198'

(3) static water level (feet) 108 below top of ground.

(4) casing PVC, 160'  
 (material) (depth)  
4"  
 (size) if telescope see back.

(5) screen 26'  
 (length) (depth to top)  
2" PVC  
 (size) (material)

(6) pump 1/2 800 gal.  
 (HP) (yield gpm)

elec.  
 (type power)

(7) electric log no  
 (yes or no)

(organization running log)

(8) how well bottom plugged

| description of formations encountered | from    | to      |
|---------------------------------------|---------|---------|
| red clay                              | 0       | 14      |
| sand & gravel                         | 14      | 36      |
| blue clay                             | 36      | 76      |
| sandy blue clay                       | 76      | 93      |
| good blue clay                        | 93      | 101     |
| sw. rock                              | 101     |         |
| blue clay                             | 101     | 105     |
| rock                                  | 105     | 105 1/2 |
| blue clay                             | 105 1/2 | 112 1/2 |
| rock                                  | 112 1/2 | 119     |
| blue clay                             | 119     | 146     |
| ground clay                           | 146     | 153     |
| blue clay                             | 153     | 156     |
| sw. rock                              | 156     |         |
| brown clay                            | 156     | 158     |
| blue clay                             | 158     | 180     |
| sand                                  | 180     | 198     |

DRILLERS REMARKS:  
Pump set 160'

DEPT. OF NATURAL RESOURCES  
 BUREAU OF LAND & WATER RESOURCES  
 SEP 30 1983  
**RECEIVED**


If well telescopes please sketch and show depths.

GROUND LEVEL

160 - 4'

17' 2" PVC

26' (20' + 6')  
Access



SECTION \_\_\_\_\_

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.