

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

WATER WELL DRILLERS LOG

CODED

46
 0216 Eln #2984
 MADISON
 1-14-85

WHEX
 MS-GW-3430

1-14 1985 Newdon Well + Supply, Inc. Madison
 date well completed firm name county well located
 Pearl, Mississippi

LANDOWNER: East Madison
 Water Assn.
 Canton, Ms. 39046
 (mailing address)

WELL LOCATION:
 sec. 8 T. 9 N. R. 4 E
 S W
 (distance) miles of (direction) (nearest town)

WELL PURPOSE: Municipal
 (home, irrigation, municipal, industrial)


WELL COMPLETION DATA:
 (1) diameter (inches) 12
 (2) total depth (feet) 1551
 (3) static water level (feet) 98 (below above top of ground.)
 (4) casing Steel, 1476 (material) (depth) (size) If telescope see back.
 (5) screen 70' 1480' (length) (depth to top) 6" SS (size) (material)
 (6) pump 40 405 (HP) (yield gpm) Electric (type power)
 (7) electric log Yes (yes or no) Newdon Well + Supply, Inc. (organization running log)
 (8) how bottom plugged: Screened

description of formations encountered	from	to
Sand/Clay	10	31
White Clay	31	59
Sand	59	145
White Clay/Sand	145	176
Sand	176	207
White Clay/Sand	207	270
Gray Sand/Lignite	270	363
Lignite/Gray Clay	363	457
Brk Clay/Shell/Br. Clay	457	488
Sh. Brown Clay	488	519
Gray Clay	519	550
Sh. Br. Peat/Br. Clay	550	580
Gray Clay/Lignite/Sand	580	611
Sand	611	642
Sand/Lignite	642	693
Clay/Sand	693	763
Brk Clay/Sand	763	784
Brk Shale/Sand	784	765
Sand/Brk Brk Shale	765	795
Sand/Lignite	795	826
Sand/Clay	826	857
Br. Clay/Sand	857	888
Sand/Clay	888	950
Sh. Brk Shale	950	1006
Brk Clay	1006	1105
Brk Clay/Sand Stone	1105	1135
Sh. Brk Shale	1135	1166
Sh Brk Shale/Brk Clay	1166	1229
Gray Clay/Sand	1229	1260
Gray Clay Silt	1260	1354
Brk Clay Silt/Sand	1354	1384
Sand	1384	1470
Clay	1470	1480
Sand	1480	1556
Clay/Sand	1556	1580
Sand	1580	1610
Clay Silt	1610	1693
Clay Silt/Sand	1693	1720

DRILLERS REMARKS:
 APR 8 - 1985

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.