

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

WATER WELL DRILLERS LOG

00000

Madison  
T65  
8-31-84

SPPT  
elv 250'

Aug. 31 1984 E.M. Brad Crosswell Madison  
date well completed firm name county well located

LANDOWNER:  
Jordan Stucky  
Brandon, Ms.  
(mailing address)

description of formations encountered	from	to
yellow clay	0	45
purple clay	45	200
shale	200	460
sand	460	475
shale	475	1030
sand	1030	1120

WELL LOCATION:  
sec. 22 8 N R 2 E  
3 miles South of Madison  
(distance) (direction) (nearest town)

WELL PURPOSE: Home  
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

(1) diameter (inches) 4

(2) total depth (feet) 1120

(3) static water level (feet) 125 below top of ground.

(4) casing steel 1090 (material) (depth)  
4 (size) If telescope see back.

(5) screen 30 1090 (length) (depth to top)  
2 stainless (size) (material)

(6) pump 1 20 (HP) (yield gpm)

(type power)

(7) electric log yes (yes or no)  
State (organization running log)

(8) how well bottom plugged  
Lead Shank


DRILLERS REMARKS:

DEPT. OF NATURAL RESOURCES  
BUREAU OF LAND & WATER RESOURCES

SEP 24 1984  
RECEIVED

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION \_\_\_\_\_

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,  
show locations of each on sketch.