

V4
6-64

WATER WELL DRILLERS LOG

CODED

Date: JUNE, 1964, Driller: MCNEECE DRILLING County MADISON
(Name Co.)

(1) Owner of Land: HINDS COUNTY WATER
(Name) CO.
JACKSON MISS.
(Address)

(2) Location: 1/4 SW 1/4, Sec. 12 87^N R1E
2 1/2 miles W of MADISON
(distance) (direction) (Nearest Town)

(3) Topography: HILLY
(Hilly) (Flat) (Level)

(4) Purpose of Well: MUNICIPAL
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
SURFACE SOIL	3	3
WHITE SHALE	25	28
GREY SHALE	386	414
SAND, SHELL & SHALE	39	453
ROCK & SHALE	8	461
LIGNITE & SAND	6	467
SHALE LIGNITE & SAND	27	494
FINE SAND	34	528
SHALE	65	593
SAND & SHALE	51	644
SAND	85	729
SHALE	4	733
SAND	26	759
SHALE	8	767
SAND (FINE) & SHALE	7	784
SHALE	38	822

Information upon completion of well:

(1) Diameter 4x2 1/2 inches.

(2) Total Depth 822 feet.

(3) Water Level 209 feet below top of ground.

(4) Cased to 406', Size 4"
406'-822' - 2 1/2"

(5) Screen: Size 2 1/2", Length 40'


(6) Were any formations sealed against pollution?
_____ yes, X no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____

CODED



(Use Back Side)

Well No. 75

100

100

100