

MADISON

MISSISSIPPI BOARD OF WATER COMMISSIONERS

W 56

3-62

WATER WELL DRILLERS LOG

CODED

Date: MARCH, 1962, Driller: MCNEECE DRILLING CO. County MADISON

(Name)

(1) Owner of Land: <u>H. S. OWENS</u> <small>(Name)</small>	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
RAYMOND RD., JACKSON MISS <small>(Address)</small>	YELLOW MARL	37	37
	GREY SHAKE	232	269
(2) Location: <u>NE 1/4, NE 1/4, Sec. 5 T7R2E</u>	SHELL SAND & SHAKE	38	307
	LIGNITE	6	313
<u>1</u> miles <u>N</u> , of <u>MADISON</u> <small>(distance) (direction) (Nearest Town)</small>	SHAKE	22	335
	SAND & SHAKE	41	376
(3) Topography: <u>HILLY</u> <small>(Hilly) (Flat) (Level)</small>	FINE SAND	92	468
	GOOD SAND	33	501
(4) Purpose of Well: <u>DOMESTIC</u> <small>(Domestic Irrigation Municipal, Industrial, Other)</small>			

Information upon completion of well:

- (1) Diameter 4 1/2" inches.
- (2) Total Depth 501 feet.
- (3) Water Level 115 feet below top of ground.
- (4) Cased to 270', Size 4"
270'-501' - 2"
- (5) Screen: Size 2", Length 20'
- (6) Were any formations sealed against pollution?


yes, X no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____

CODED



(Use Back Side)

Well No. 29

1950

1950