

Marshall
K8
12-4-69

MISSISSIPPI **DODED**
 BOARD OF WATER COMMISSIONERS
 416 North State Street
 Jackson, Mississippi 39201
 WATER WELL DRILLERS LOG

12-4-1969 date well completed
 Thoepe Well Supply Co firm name
 Marshall county well located

LANDOWNER: Teresa & Mary Lester
Rt #3 Box 196 A
Holly Springs, Miss.
 (mailing address)

description of formations encountered	from	to
To P Soil	0	10
Red fine Sand	10	55
White med SAND	55	85
" COARSE "	85	132
White clay	132	146
" FINE SAND	146	156
" FINE " + clay mix	156	166
" Med SAND	166	185
White COARSE SAND	185	205

WELL LOCATION:
 sec 29 T 3 N R 3 E
3 miles SE of Red Banks
 (distance) (direction) (nearest town)

WELL PURPOSE:
 (home) irrigation, municipal, industrial

- WELL COMPLETION DATA:
- (1) diameter (inches) 4"
 - (2) total depth (feet) 205
 - (3) static water level (feet) 120 ^{below} above top of ground.
 - (4) casing PVC (NSF) 201'
 (material) (depth)
 (size) If telescope see back.
 - (5) screen 4' 201'
 (length) (depth to top)
4" PVC FILTER PACK
 (size) (material)
 - (6) pump 1/3 8
 (HP) (yield gpm)
220 SP.
 (type power)
 - (7) electric log NO
 (yes or no)


(organization running log)
 (8) how well bottom plugged End
at screen 4" cap.

DRILLERS REMARKS:

APR - 8 1970
MISS. BD. WATER C.

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.