

MONROE MISSISSIPPI BOARD OF WATER COMMISSIONERS

C 37  
7-26-65

Coded

WATER WELL DRILLERS LOG

Date: July 26, 1965, Driller: Layne-Central Co. County Monroe  
(Name)

(1) Owner of Land: True Temper Corp.  
(Name) -  
Amory, Miss.  
(Address)  
Sw SE  
(2) Location: 1/4, 1/4, Sec. 36 T12R19W  
(distance) (direction) (Nearest Town)  
(3) Topography: (Hilly) (Flat) (Level)  
(4) Purpose of Well: Industrial  
(Domestic Irrigation  
Municipal, Industrial, Other)


Information upon completion of well:

(1) Diameter 16 inches.  
(2) Total Depth 305 feet.  
(3) Water Level ? feet below top of ground.  
(4) Cased to 235', Size 10"  
(5) Screen: Size 10", Length 60'  
(6) Were any formations sealed against pollution?  
x yes, no.

If YES depth of formation 235'  
Why required

Drillers Remarks:

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
red sand-clay	8	8
coarse gravel-sand	14	22
hard blue clay	8	30
soft sandy clay	22	52
fine pack sand	4	56
hard rock	4	60
hard sand rock	10	70
blue clay	18	88
sandy clay-gravel	6	94
hard-soft clay	22	116
hard sand rock	1	117
hard blue clay	21	138
hard white chalk	1	139
hard blue clay	12	151
coarse sand	6	157
blue sandy clay	12	169
fine sand	2	171
blue sandy clay	8	179
sand with little clay	24	203
blue clay	13	216
sand-clay stk.	18	234
sand-gravel	40	274
blue clay - hard	1	275
sand-gravel	11	286
sand-gravel little clay	30	316



Well No.

(4)