

MONROE

P46

6-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

**CODED**

Date: 6-25, 1966, Driller: J. C. REEVES County MONROE

(When well drilled)

(Name)

(Where well is located)

(1) Owner of Land: ARNET KING  
 (Name)  
RT. 4, ABERDEEN  
 (Address)

(2) Location: SE 1/4, NW 1/4, Sec. 35 T15R 7  
9 miles S of ABERDEEN  
 (distance) (direction) (Nearest Town)

(3) Topography: HILLY  
 (Hilly) (Flat) (Level)

(4) Purpose of Well: DOMESTIC  
 (Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>YELLOW CLAY</u>	<u>8</u>	<u>0</u>
<u>LIME ROCK</u>	<u>4</u>	<u>8</u>
<u>BLUE CLAY</u>	<u>12</u>	<u>12</u>
<u>" SAND</u>	<u>13</u>	<u>25</u>
<u>" CLAY</u>	<u>8</u>	<u>33</u>
<u>" SAND</u>	<u>21</u>	<u>45</u>
<u>" CLAY</u>	<u>5</u>	<u>66</u>
<u>" SAND</u>	<u>2</u>	<u>71</u>
<u>" CLAY</u>	<u>5</u>	<u>73</u>
<u>" SAND</u>	<u>2</u>	<u>78</u>
<u>" CLAY</u>	<u>20</u>	<u>80</u>
<u>HARD ROCK</u>	<u>1</u>	<u>100</u>
<u>BLUE CLAY</u>	<u>29</u>	<u>101</u>
<u>HARD ROCK</u>	<u>4"</u>	<u>130</u>
<u>BLUE CLAY</u>	<u>2</u>	<u>130</u>
<u>HARD ROCK</u>	<u>4"</u>	<u>132</u>
<u>BLUE CLAY</u>	<u>13</u>	<u>132</u>
<u>" SAND</u>	<u>15</u>	<u>145</u>
<u>" CLAY</u>	<u>2</u>	<u>160</u>
<u>" SAND</u>	<u>14</u>	<u>162</u>
<u>" CLAY</u>	<u>38</u>	<u>176</u>
<u>" SAND</u>	<u>22</u>	<u>214</u>
<u>" CLAY</u>	<u>17</u>	<u>238</u>
<u>BLUE CLAY &amp; SAND</u>	<u>10</u>	<u>255</u>

Information upon completion of well:

(1) Diameter 4 inches.

(2) Total Depth 265 feet.

(3) Water Level 120 feet below top of ground.

(4) Cased to 42', Size 4"

(5) Screen: Size none, Length -

(6) Were any formations sealed against pollution?  
 yes,  no.

If YES depth of formation \_\_\_\_\_


Why \_\_\_\_\_

Drillers Remarks: \_\_\_\_\_

Yield in gpm: 15

Size pump: 1 HP. JET

Type power: ELECTRIC



[The page contains extremely faint and illegible text, likely bleed-through from the reverse side of the document. The text is too light to transcribe accurately.]