

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

CODED

WATER WELL DRILLERS LOG

MONROE
Q 81
6/8/83

6-8 1983 Clardy Well Drilling Monroe
date well completed firm name county well located

LANDOWNER: Thornon-Montent
2220 One Dallas Center
Dallas, Texas 75201
(mailing address)

WELL LOCATION:
sec. 13 T. 16 N. R. 17 E.
9 miles SE of Abbeville
(distance) (direction) (nearest town)

WELL PURPOSE: industrial
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

(1) diameter (inches) 4"
(2) total depth (feet) 320'
(3) static water level (feet) 28' below above top of ground.
(4) casing PVC, 136'
(material) (depth)
4" if telescope see back.
(size)
(5) screen 50'
(length) (depth to top)
2' PVC
(size) (material)
(6) pump 5 3500 gph
(HP) (yield-gpm)
elec. 58 gpm
(type power)
(7) electric log DEPT. OF NATURAL RESOURCES
(yes or no) BUREAU OF LAND & WATER RESOURCES
(organization running well) Jul 28 1983
(8) how well bottom logged

description of formations encountered	from to	
red clay	0	9
sand & gravel	9	18
hard blue clay	18	39
sandy clay	39	48
hard clay	40	67
sandy clay	67	71
brown clay	71	78 1/2
rock	78 1/2	79
brown clay	79	86
rock	86	87
brown clay	87	92
hard blue clay	92	109
rock	109	109 1/2
hard blue clay	109 1/2	126
sandy clay	126	129
good clay	129	131
rock	131	133
good clay	133	154
rock 3"	154	
sand	154	160 1/2
rock 2"	160 1/2	
sand	160 1/2	164
sandy clay	164	168
rock	168	168 1/2
sandy clay	168 1/2	174
good clay	174	176
rock	176	178 3/4
rock	178 3/4	179
good clay	179	208
brown clay	208	238
sand	238	260
good sand	260	265
sandy clay	265	269
good sand	269	280
sandy clay	280	297
good sand	297	303
sandy clay	303	306
good sand	306	313
hard clay	313	320

DRILLERS REMARKS:

CODED

RECEIVED


If well telescopes please sketch and show depths.

GROUND LEVEL

136' - 4"

144' - 0"

50' Screen



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.