

NESHOMA
E 27
10-4-62

WATER WELL DRILLERS LOG

CODED

Date: 10-4, 1962, Driller: R.R. Nicholson County: Neshoba
PR-33 Sarah Dixon (Name)

(1) Owner of Land: U.S. Govt.
(Name)
Phila. Miss.
(Address)
4 11 50
(2) Location: 1/4, 1/4, Sec. T R
11 miles West of Phila.
(distance) (direction) (Nearest Town)
(3) Topography: Hilly
(Hilly) (Flat) (Level)
(4) Purpose of Well: Domestic
(Domestic Irrigation
Municipal, Industrial, Other)


Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet.
Chalky Clay	0	28
rock	28	50
blue dirt & sand	50	60
Shell & rock	60	120
blue dirt	120	200
Shell & rock	200	260
blue dirt & sand	260	278
water sand	278	298

Information upon completion of well:

(1) Diameter 3 7/8 inches.
(2) Total Depth 298 feet.
(3) Water Level 175 feet below top of ground.
(4) Cased to Joint, Size 2"
(5) Screen: Size 2", Length 10ft
(6) Were any formations sealed against pollution?
yes, no.

If YES depth of formation 11ft 4" pipe
Why Sanitary Purpose
Drillers Remarks: Cylinder set
at 200ft

CODED



(Use Back Side)

Well No.

2000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01

1000 11.01