

NEWTON  
 B3  
 9-13-63

WATER WELL DRILLERS LOG

CODED

Date: 9-13-, 19\_\_, Driller: Layne-Central Co. County Newton

(Name)

(1) Owner of Land: Town of Union  
 (Name)  
Union, Mississippi  
 (Address)

(2) Location: 1/4, 1/4, Sec. 1811  
TR  
 \_\_\_\_\_ miles \_\_\_\_\_ of \_\_\_\_\_  
 (distance) (direction) (Nearest Town)

(3) Topography: \_\_\_\_\_  
 (Hilly) (Flat) (Level)

(4) Purpose of Well: Municipal  
 (Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
top soil	1	1
red sandy clay, hard	9	10
rock	1	11
blue clay	7	18
blue sand	2	20
rock, sand stks	5	25
hard brittle clay	8	33
hard rock	12	45
hard brittle clay	11	56
rock	3	59
hard brittle clay	6	65
hard rock, soft stks	40	105
hard blue shale	33	138
sand	105	243
clay	4	247

Information upon completion of well:

(1) Diameter 16" inches.

(2) Total Depth 242' feet.

(3) Water Level 90' feet below top of ground.


(4) Cased to 180', Size 16"

(5) Screen: Size 8", Length 50'

(6) Were any formations sealed against pollution?  
 yes, \_\_\_\_\_ no.

YES, depth of formation 180'  
 \_\_\_\_\_ required

CODED



Drillers Remarks: \_\_\_\_\_

(Use Back Side)

Well No.

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...