

OKtibbleha

C 21  
8-65

MISSISSIPPI BOARD OF WATER COMMISSIONERS

MS-65-1336

LOG # 40

WATER WELL DRILLERS LOG

CODED

Date: 8-23-1965, Driller: Layne-Central Co. County: Oktibbeha

(Name)

(1) Owner of Land: City of Starkville  
(Name)  
Starkville, Mississippi  
(Address)

(2) Location: 1/4, 1/4, Sec. T R  
miles of  
(distance) (direction) (Nearest Town)

(3) Topography:  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Municipal  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Red clay	8	8
blue lime	390	398
hard lime	122	520
soapstone	34	554
hard rock	2	556
lime	64	620
brittle clay	78	698
clay	52	750
sandy shale	112	862
hard shale	18	880
sandy shale-hard stks	164	1044
rock	1	1045
hard shale-soft stks	63	1108
hard shale	14	1122
shale-sand stks	52	1174
hard shale	51	1225
shale-sand stks	48	1273
hard lime	17	1290
brittle shale-sand stks	29	1319
sand with stks	11	1330
rock	26	1356
hard lime	39	1395
sand	30	1425
hard limey shale	23	1448
sand-stks lime	13	1461
hard lime	7	1468
sand	23	1491
sand	23	1514
sand	7	1521
sand rock	2	1523

Information upon completion of well:

(1) Diameter 16 inches.

(2) Total Depth 1521' feet.

(3) Water Level 172 feet below top of ground.

(4) Cased to 1450', Size 16"


(5) Screen: Size 10", Length 60'

(6) Were any formations sealed against pollution?  
X yes, no.

If YES depth of formation 1450'

Why required sand

Drillers Remarks:



Well No.

