

PEARL RIVER
M 2013
10-19-78

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

WATER WELL DRILLERS LOG

TOM GRIFFITH

PLUMBING & WELL SERVICE, INC.

Paul Reeves
county well located

10-19-78
date well completed

LANDOWNER:

Mr. Emanuel Abram
Pt. 1 Box 98
Paplarville, Miss.
(mailing address)

WELL LOCATION:

sec. 9 T 3 N R 15 E
2 miles *South of town*
(distance) (direction) (nearest town)

WELL PURPOSE: *Home*
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 2"
- (2) total depth (feet) 253 ft.
- (3) static water level (feet) 120 below above top of ground.
- (4) casing Plastic, 233
(material) (depth)
2"
(size) If telescope see back.
- (5) screen 20 ft., 213
(length) (depth to top)
2", Plastic
(size) (material)
- (6) pump 2 HP, 8
(HP) (yield gpm)
Electric
(type power)
- (7) electric log No
(yes or no)

(organization running log)

(8) how well bottom plugged Back Wash Valve

DRILLERS REMARKS:

description of formations encountered

from to


<i>Top Soil</i>	<i>0</i>	<i>1</i>
<i>Clay</i>	<i>1</i>	<i>6</i>
<i>Gravel & Sand</i>	<i>6</i>	<i>29</i>
<i>Sand</i>	<i>29</i>	<i>42</i>
<i>Clay</i>	<i>42</i>	<i>91</i>
<i>Sand</i>	<i>91</i>	<i>105</i>
<i>Clay</i>	<i>105</i>	<i>180</i>
<i>Sand & Gravel</i>	<i>180</i>	<i>202</i>
<i>Sand</i>	<i>202</i>	<i>233</i>

RECEIVED 50

DEC 13 1978

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.