

U-36
11-11-62

WATER WELL DRILLERS LOG

CODED
County Waver

Date: Nov. 11, 1962, Driller: M&B Drilling Co.
(Name) 520-37

(1) Owner of Land: Robert Welch
(Name)
Carrier, Miss.
(Address)

(2) Location: 1/4 1/4, Sec. 13 T. 5R E. 7
West of Play Road
miles Center of of Carrier
(distance) (direction) (Nearest Town)

(3) Topography: Hilly
(Hilly) (Flat) (Level)

(4) Purpose of Well: Home
(Domestic Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Hard Red Clay</u>	<u>14</u>	<u>14</u>
<u>White Sand</u>	<u>50</u>	<u>64</u>
<u>Soft White Clay</u>	<u>20</u>	<u>84</u>
<u>Hard White Clay</u>	<u>26</u>	<u>110</u>
<u>Blue Clay</u>	<u>125</u>	<u>235</u>
<u>Grey Sand (Fine)</u>	<u>10</u>	<u>245</u>
<u>Blue Clay</u>	<u>65</u>	<u>310</u>
<u>Grey Sand (Fine)</u>	<u>16</u>	<u>326</u>
<u>Black Pink Clay (Hard)</u>	<u>149</u>	<u>475</u>
<u>Grey Sand</u>	<u>40</u>	<u>515</u>
<u>Blue Clay</u>		<u>515</u> <u>on</u>

Information upon completion of well:


- (1) Diameter 2 inches.
- (2) Total Depth 510 feet.
- (3) Water Level 68 feet below top of ground.
- (4) Cased to 500, Size 2"
- (5) Screen: Size 2" 85/16", Length 10 FT.
- (6) Were any formations sealed against pollution?
_____ yes, _____ no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____

CODED



(Use Back Side)

Well No.

Handwritten notes, possibly bleed-through from the reverse side of the page. The text is extremely faint and illegible.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100