

U.S. 5  
10-66

WATER WELL DRILLERS LOG

Date: 10-28, 1966, Driller: Walter Penton County Pearl River

(Name)

(1) Owner of Land: Mr Charles Shearh  
Rt. 2 Box 46 (Name)  
Carriere Miss  
(Address)

(2) Location: SW 1/4, SE 1/4, Sec. 26 T5 R17, S W  
2 miles North, of Pecayune, (direction) (Nearest Town)

(3) Topography: Flat (Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic (Domestic Irrigation Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Red Clay	23	0-23
Sand + mud	46	69
Blue Clay	146	215
Grey sand	28	243
Blue Clay	31	274
" Mud	20	294
Grey sand	118	412
Blue Clay	237	649
Grey sand		704

Information upon completion of well:


- (1) Diameter 2 inches.
- (2) Total Depth 704 feet.
- (3) Water Level 3 feet below top of ground.
- (4) Cased to 694, Size 2"
- (5) Screen: Size 2" .012, Length 10'
- (6) Were any formations sealed against pollution?

yes, no.

If YES depth of formation

Why

Drillers Remarks: Did not cut to bottom of sand at 704



Well No.

(Use Back Side)

