

CODED

MISSISSIPPI BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

Pearl River
W 148
2-67

130

WATER WELL DRILLERS LOG

2-13 date well completed 67 Penton Well Serv firm name Pearl River county well located

LANDOWNER: Olivia Keller

Rt. 1, Box 148

Picayune, Miss.
(mailing address)

WELL LOCATION:

sec 3 T 7 S R 17 W
0 miles South of Nicholson
(distance) (direction) (nearest town)

WELL PURPOSE: Home
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

(1) diameter (inches) 2"

(2) total depth (feet) 1008

(3) static water level (feet) Flow below above top of ground.

(4) casing Black Steel, 988
(material) (depth)

if telescope see back.
(size)

(5) screen 20', 988
(length) (depth to top)

.012 2", Stainless Steel
(size) (material)

(6) pump 60
(HP) (yield gpm)

(type power)

(7) electric log NO
(yes or no)


(organization running log)

(8) how well bottom plugged B.W. Valve

DRILLERS REMARKS:

description of formations encountered	from	to
	Yellow Clay	0
White Sand	18	34
Sand & Gravel	34	115
Blue Clay	115	260
Grey Sand	260	357
Blue Clay	357	424
Grey Sand	424	532
Blue Clay	532	705
Grey Sand	705	740
Blue Clay	740	823
Grey Sand	823	853
Blue Clay	853	890
Grey Sand	890	1008

CODED



If well telescopes please sketch and show depths.

GROUND LEVEL

			X

SECTION 3

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.