

Pearl River
 W 152
 12-67

MISSISSIPPI
 BOARD OF WATER COMMISSIONERS
 416 North State Street
 Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

12-29 1967 Penton Well Serv Pearl River
 date well completed firm name county well located

LANDOWNER: Ray Henderson

Nicholson

MISS

(mailing address)

WELL LOCATION:

sec. 34 T. 6 S. R. 17 W.
0 miles East of Nicholson
 (distance) (direction) (nearest town)

WELL PURPOSE: Home
 (home, irrigation, municipal, industrial)


WELL COMPLETION DATA:

- (1) diameter (inches) 4 1/2
- (2) total depth (feet) 965
- (3) static water level (feet) Flow ⁺³⁹ below top of ground.
- (4) casing Black steel 945'
 (material) (depth)
2" if telescope see back.
 (size)
- (5) screen 20', 945'
 (length) (depth to top)
.015 2", S. Steel
 (size) (material)
- (6) pump (HP) _____ (yield gpm)
 _____ (type power)
- (7) electric log NO
 (yes or no)
 _____ (organization running log)
- (8) how well bottom plugged B.W. Valve

description of formations encountered

from to

Clay	0	18
Sand + Gravel	18	92
Blue clay	92	200
Black Mud	200	240
Grey sand	240	287
Blue Clay	287	340
Grey sand	340	352
Blue Clay	352	428
Grey sand	428	522
Blue Clay	522	680
MADE	680	728
Blue clay	728	865
Fine Grey sand	865	920
Rock	920	922
Grey sand + Gravel	922	965



DRILLERS REMARKS:

16# Pressure at Ground level

If well telescopes please sketch and show depths.

GROUND LEVEL

		X	

SECTION 34

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.