


MISSISSIPPI DEPARTMENT OF ENVIRONMENT QUALITY

Office of Land and Water Resources
 P.O. Box 2309
 Jackson, MS 39225
 Water Well Plugging/Decommissioning Form
 OLWR-DF-1 (4/08)

COUNTY WELL LOCATED	Pike	WELL NUMBER:	A0002
PERMIT NUMBER:	MS-GW-01847	DATE WELL PLUGGED:	11/06/2012
NAME OF FIRM PLUGGED WELL	Mid-South Water and Machine Works, LLC TELEPHONE NUMBER (662) 843-4076		
NAME AND ADDRESS OF CURRENT LANDOWNER	Town of Summit P. O. Box 517 Summit, MS 39666		
WELL LOCATION	SECTION: 26	TOWNSHIP: 04N	RANGE 07E
WELL LOCATION LATITUDE	N31° 17' 5.842"	LONGITUDE	W90° 28' 4.184"
METHOD (CIRCLE ONE) (1) USGS QUAD (2) CONVENTIONAL SURVEY (3) GPS - HAND HELD OR SURVEY GRADE			
DISTANCE	100'	DIRECTION	East NEAREST TOWN Hwy 51 OTHER LANDMARK on Peters St.
WELL PURPOSE (HOME, IRRIGATION, MUNICIPAL ETC.)	Municipal		
NAME OF WELL CONTRACTOR WHO DRILLED THE WELL:	Layne		
NAME OF LANDOWNER WHEN WELL WAS DRILLED:	Town of Summit		

WELL DATA			
WELL DEPTH:	104'	HOLE DEPTH:	
CASING DIAMETER (IN)	8"	CASING LENGTH (FT)	60"
		TYPE OF CASING	Steel
DEPTH TO STATIC WATER LEVEL:	35'	DATE WELL COMPLETED:	1937
WHY IS THE WELL BEING ABANDONED?	Does not produce water		

DESCRIBE HOW THE WELL OR HOLE WAS PLUGGED (AMOUNT OF CASING AND/OR SCREEN THAT WAS REMOVED OR LEFT IN HOLE. MATERIAL AND AMOUNT USED IN PLUGGING METHOD OF PLACING MATERIAL ETC.)
Pulled pump from the well.
Ran 100' of pipe into well.
Pumped 6yd ³ of cement into the well.
Obtained cement returns at ground surface.
Well located inside of building.
Pump foundation part of building floor, left in place.

CERTIFY THAT THE WELL WAS PLUGGED OR ABANDONED IN ACCORDANCE WITH THE STATE OF MISSISSIPPI REGULATIONS	
Clayton Miller PRINT NAME	0-703 MS LICENSE NUMBER
 SIGNATURE	11-20-2012 DATE