

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

WATER WELL DRILLERS LOG

PIKE
L 2091

9-14 1994 Amite Pump Well PIKE
date well completed firm name county well located

#0-235

LANDOWNER: Keith J.C. Williams
1143 Bouding Light Rd.
MARSHALL, MS. 39652
(mailing address)

description of formations encountered	from	to
CLAY	0	30
Clay + Gravel	30	60
GRAVEL	60	70
Clay	70	115
COARSE SAND + GRAVEL	115	130

WELL LOCATION:
sec. 9 T. 1 N. R. 8 E
3.5 miles E of CHATAWA
(distance) (direction) (nearest town)


WELL PURPOSE: Home
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 4
- (2) total depth (feet) 130
- (3) static water level (feet) 60 below top of ground.
- (4) casing ^{Sch 40} PVC (material), 120 (depth), 4 (size) If telescope see back.
- (5) screen 10 (length), 120 (depth to top), .014 (size), Sch 40 PVC Slotted (material)
- (6) pump 1/2 (HP), N/A (yield gpm), Electric (type power)
- (7) electric log NO (yes or no)

(organization running log)
(8) how well bottom plugged Backwash Valve

DRILLERS REMARKS:



OCT 14 1994

Dept. of Environmental Quality
Office of Land & Water Resources

If well telescopes please sketch and show depths.

GROUND LEVEL

		X	

SECTION 9

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.