

QUITMAN  
C

WATER WELL DRILLERS LOG

Date: 4-19, 1961, Driller: DELTA DRILLING Co County LEFLORE  
 4-19-61 (Name)

(1) Owner of Land: J. W. LOLLAR  
 (Name)  
DARLING MISS  
 (Address)

(2) Location: 1/4, 1/4, Sec. T R R  
 miles \_\_\_\_\_ of \_\_\_\_\_  
 (distance) (direction) (Nearest Town)

(3) Topography: \_\_\_\_\_  
 (Hilly) (Flat) (Level)

(4) Purpose of Well: DOMESTIC  
 (Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
CLAY	18	18
SAND	68	86
GRAVEL	65	151
GUMBO	63	214
SAND	134	348
GUMBO	78	426
SHELL	42	468
GUMBO	43	511
SHELL	63	574
GREEN SAND w/1/4" ROCK	40	614
SHELL	67	681
SAND	17	698
SHELL	76	774
WHITE SAND	28	802
GUMBO	22	824
SHELL	63	887
FINE SAND	37	924
SHELL	47	971
GUMBO	7	978
WHITE SAND	40	1018

Information upon completion of well:

(1) Diameter 3 inches.

(2) Total Depth 1018 feet.

(3) Water Level \_\_\_\_\_ feet below top of ground.

(4) Cased to 1018, Size 3+2"


(5) Screen: Size 2", Length 30'

(6) Were any formations sealed against pollution?  
 \_\_\_\_\_ yes,  no.

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: 22' LAP OF 2"  
IN 3" PIPE - 1-2" LEAD  
SEAL 489'



Well No.

(Use Back Side)

