

**MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY**  
**Office of Land and Water Resources**  
 P. O. Box 10631  
 Jackson, MS 39289  
**Water Well Plugging/Decommissioning Form**  
 OLWR-DF-1 (1/03)


COUNTY WELL LOCATED: <u>Quitman</u>		WELL NUMBER: <u>0</u>
PERMIT NUMBER: <u>GW-36312</u>	DATE WELL PLUGGED: <u>2012</u>	
NAME OF FIRM PLUGGING WELL: <u>Circle S IRRIGATION</u>	TELEPHONE NUMBER: <u>662-627-7246</u>	
NAME AND ADDRESS OF CURRENT LANDOWNER: <u>DENON FAENS</u> <u>PRAIRIE 200</u> <u>MARKS, MS 38646</u>		
WELL LOCATION:	SECTION: <u>35</u>	TOWNSHIP: <u>28N</u> RANGE: <u>2W</u>
WELL LOCATION: LATITUDE: <u>34°15' 12"</u>	LONGITUDE: <u>90°22' 21"</u>	METHOD (CIRCLE ONE): (1) USGS QUAD (2) CONVENTIONAL SURVEY (3) GPS - HAND HELD OR SURVEY GRADE
DISTANCE: <u>2 1/4</u>	DIRECTION: <u>NVE</u>	NEAREST TOWN: <u>BARNSDALE</u> OTHER LANDMARK:
WELL PURPOSE (HOME, IRRIGATION, MUNICIPAL, ETC.): <u>IRRIGATION</u>		
NAME OF WELL CONTRACTOR WHO DRILLED THE WELL:		
NAME OF LANDOWNER WHEN WELL WAS DRILLED:		

WELL DATA		
WELL DEPTH: <u>115</u>	HOLE DEPTH: <u>110</u>	
CASING DIAMETER (IN.): <u>10</u>	CASING LENGTH (FT.): <u>80</u>	TYPE OF CASING: <u>STEEL</u>
DEPTH TO STATIC WATER LEVEL:	DATE WELL COMPLETED:	
WHY IS THE WELL BEING ABANDONED? <u>WELL WAS BAD</u>		

DESCRIBE HOW THE WELL OR HOLE WAS PLUGGED (AMOUNT OF CASING AND/OR SCREEN THAT WAS REMOVED OR LEFT IN HOLE, MATERIAL AND AMOUNT USED IN PLUGGING, METHOD OF PLACING MATERIAL, ETC.)

PUT 2 CUBIC YARDS OF SAND & GRAVEL ALONG WITH .5 POUNDS OF CHLORINE TABLETS. REMOVED 3 FEET OF DIRT FROM AROUND WELL, FILLED CASING & AREA AROUND WELL WITH BENTONITE. CUT CASING OFF 3 FEET BELOW GROUND LEVEL.

I CERTIFY THAT THE WELL WAS PLUGGED OR ABANDONED IN ACCORDANCE WITH THE STATE OF MISSISSIPPI REGULATIONS.

DAVID P. HOLT  
  
 SIGNATURE

0-752P  
 MS LICENSE NUMBER  
8-25-12  
 DATE

**RECEIVED**  
**AUG 27 2012**  
**BY: OLWR**

12-504