

**QUITMAN**  
**H39**  
**9-28-73**

**MISSISSIPPI**  
**BOARD OF WATER COMMISSIONERS**  
 416 North State Street  
 Jackson, Mississippi 39201

**WATER WELL DRILLERS LOG**

9-28 1973 FIVE COUNTY FARMERS ASSN QUITMAN  
 date well completed firm name county well located

LANDOWNER: Wade Inc.

MARKS, Miss.

(mailing address)

**WELL LOCATION:**

sec. 11 T. 37 (N) R. 1 E. (W)  
1 1/2 miles South of MARKS  
 (distance) (direction) (nearest town)

**WELL PURPOSE: INDUSTRIAL**  
 (home, irrigation, municipal, industrial)

**WELL COMPLETION DATA:**

- (1) diameter (inches) 4" x 3"
- (2) total depth (feet) 840'
- (3) static water level (feet) 10'  below  above top of ground.
- (4) casing GALV. PIPE, 800'  
 (material) (depth)  
 \_\_\_\_\_ if telescope see back.  
 (size)
- (5) screen 40', 800'  
 (length) (depth to top)  
3", Stainless steel 10 slot  
 (size) (material)
- (6) pump 2 HP 40 gpm  
 (HP) (yield gpm)  
electric  
 (type power)
- (7) electric log No  
 (yes or no)
- (8) how well bottom plugged Back  
Wash Vowes

description of formations encountered

from to

<u>Sand &amp; sea gravel</u>	<u>0</u>	<u>110</u>
<u>Blue Mud</u>	<u>110</u>	<u>400</u>
<u>Sand &amp; lignite</u>	<u>400</u>	<u>450</u>
<u>Heavy Mud</u>	<u>450</u>	<u>600</u>
<u>Rock Hard Clay</u>	<u>600</u>	<u>690</u>
<u>Sand</u>	<u>700</u>	<u>720</u>
<u>Clay</u>	<u>720</u>	<u>800</u>
<u>Water Sand</u>	<u>800</u>	<u>840</u>


**CODED**

DRILLERS REMARKS:

**OCT 20 1973**

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION \_\_\_\_\_

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,  
show locations of each on sketch.