

B7
8-13-62

WATER WELL DRILLERS LOG

Forest Drilling

CODED

Date: 8/13, 1962, Driller: James McGee County: Rankin.
(Name)

(1) Owner of Land: Clyde D. Flemming
(Name)
Sand Hill, Miss.
(Address)

(2) Location: 1/4, 1/4, Sec. 28 TR 5
8 miles East of Sand Hill
(distance) (direction) (Nearest Town)
Tena

(3) Topography: X
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
(Domestic Irrigation
Municipal, Industrial, Other)

| Description & Color of Materials Sand, Clay, Red Clay, Shell, etc. | Thick- ness Feet | Depth Feet |
|---|------------------------|---------------|
| Brown clay.. | 27- | 27 |
| Blue clay. | 35- | 62 |
| Clay & lime rock. | 10- | 72 |
| Clay & lime. | 20- | 92 |
| Clay & stks. fine sand. | 10- | 102 |
| Clay. | 20- | 122 |
| Fine sand & stks. clay. | 20- | 142 |
| Clay. | 25- | 167 |
| Clay & fine sand. | 5- | 172 |
| Fine sand & stks. clay. | 25- | 197 |
| Clay & stks. fine sand. | 15- | 212 |
| Clay. | 6- | 218 |
| Fine sand. | 27- | 245 |
| Clay. | 4- | 249 |
| Fine sand. | 23- | 272 |
| Clay. | 7- | 279 |
| Fine sand. | 63- | 342 |
| Sand & clay. | 8- | 350 |
| Sand. (Screen setting.) | 22- | 372 |
| Clay. | 10- | 382 |

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 372 feet.

(3) Water level 54 feet below top of ground.


(4) Cased to 362', Size 2"

(5) Screen: Size 2", Length 10'

(6) Were any formations sealed against pollution?
no yes, X no.

If YES depth of formation _____
Why _____

Drillers Remarks: Good well.



FOREST DRILLING SERVICE
P. O. Box 5717
PEARL BRANCH
JACKSON 8, MISS.

*Conrad
L...
JES*

(Use Back Side)

Well No.

