

6-9-61 29

WATER WELL DRILLERS LOG

CODED

Date: 6/9, 1961, Driller: Johnnie Beasley County Rankin
(Name)

(1) Owner of Land: W. S. Torrence
(Name)
 This well located North of Brandon
 Brandon, Miss.
 about 10 miles on Hwy. 471 73
(Address)
 (2) Location: 1/4, 1/4, Sec. 26 T. R
10 miles North of Brandon
(distance) (direction) (Nearest Town)
 (3) Topography: X
(Hilly) (Flat) (Level)
 (4) Purpose of Well: Domestic.
(Domestic Irrigation Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Yellow clay.	0-	35
Blue clay.	35-	205
Blue shale.	205-	307
Sahle, sand & coal.	307-	327
Shale & silt.	327-	388
Fine sand & stks. shale.	388-	410
Shale & silt.	410-	428
Sand.	428-	432
Shale.	432-	538
Sand & stks. shale.	538-	556
Shale.	556-	568
Sand & stks. shale.	568-	620
Sand. (Screen setting)	620-	640

Information upon completion of well:


- (1) Diameter 2 inches.
- (2) Total Depth 640' feet.
- (3) Water Level 95' feet below top of ground.
- (4) Cased to 630', Size 2"
- (5) Screen: Size 2", Length 10'
- (6) Were any formations sealed against pollution?
no yes, X no.

If YES depth of formation _____

Why _____

Drillers Remarks: Good well.

CODED



(Use Back Side)

Well

