

Rankin
G 13
9-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

CODED

WATER WELL DRILLERS LOG

Date: 9/1, 1966, Driller: Forest Willing County, Rankin
(Name)

(1) Owner of Land: Charles Belmont
(Name)
Rt 3 Brandon, Miss.
(Address)

(2) Location: NE 1/4, NE 1/4, Sec 24 T6N R3E
8 miles North of Brandon
(distance) (direction) (Nearest Town)

(3) Topography: (Hilly) (Flat) (Level)

(4) Purpose of Well: Chicken House
(Domestic Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Brown Clay</u>	<u>32</u>	<u>32</u>
<u>Blue Clay</u>	<u>277</u>	<u>309</u>
<u>Shale + Sths Rock</u>	<u>20</u>	<u>329</u>
<u>Shale</u>	<u>42</u>	<u>371</u>
<u>Shale + Sths Sandy Shale</u>	<u>20</u>	<u>391</u>
<u>Shale</u>	<u>20</u>	<u>411</u>
<u>Hard Shale</u>	<u>62</u>	<u>473</u>
<u>Shale + Sths Sand</u>	<u>41</u>	<u>514</u>
<u>Fire Sand + Sths Shale</u>	<u>20</u>	<u>534</u>
<u>Fire Sand + Sths Clay</u>	<u>21</u>	<u>555</u>
<u>Fire Sand</u>	<u>41</u>	<u>596</u>
<u>Shale + Sths Sand</u>	<u>14</u>	<u>610</u>
<u>Fire Sand</u>	<u>23</u>	<u>633</u>

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 633 feet.

(3) Water Level 179 feet below top of ground.

(4) Cased to 618, Size 2"

(5) Screen: Size 2", Length 15 ft.


(6) Were any formations sealed against pollution?
_____ yes, no.

CODED

If YES depth of formation _____

Why _____

Drillers Remarks: _____



(Use Back Side)

Well No.

