

RANKIN

G 17

4-21-62

WATER WELL DRILLERS LOG

CODED

(21) Rankin
Forest

Date: 4/21, 1962, Drillers Forest Drilling Co. County Rankin

(Name) Set pump 5/15/62

(1) Owner of Land: George Calhoun
(Name)

Rt 3 Brandon, Miss
(Address)

(2) Location: 1/4, 1/4, Sec 13 T6 R3

7 miles North of Brandon
(distance) (direction) (Nearest Town)

(3) Topography: Level
(Hilly) (Flat) (Level)

(4) Purpose of Well: Chicken Houses
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>0-32ft Brown Clay</u>		
<u>32-159 Blue Clay</u>		
<u>159-304 Shale</u>		
<u>304-314 Shale + (thk)</u>		
<u>thin limy rock</u>		
<u>314-324 Clay + Shale</u>		
<u>324-350 Sandy Shale + Rock</u>		
<u>350-389 Clay</u>		
<u>389-399 Clay + fine sand</u>		
<u>399-439 Clay + (thk) fine sand</u>		
<u>439-469 fine sand</u>		
<u>469-472 Clay</u>		

Information upon completion of well:

(1) Diameter 2" inches.

(2) Total Depth 472 feet.

(3) Water Level 103 feet below top of ground.

(4) Cased to 457, Size 2"

(5) Screen: Size 2", Length 15ft.


(6) Were any formations sealed against pollution?
no

If YES depth of formation _____

Why _____

Drillers Remarks: _____

CODED



FOREST DRILLING SERVICE
231 Highway 30 North
FOREST, MISSISSIPPI

(Use Back Side)

Well No.

1000

1000

44

1000

1000

1000

1000