

RANKIN MISSISSIPPI BOARD OF WATER COMMISSIONERS

K 112
10-15-63

WATER WELL DRILLERS LOG **CODED**

Date: 10/15, 1963, Driller: Forest Belgard County: Franklin
(Name)

(1) Owner of Land: J.W. Patrick
(Name)
4 miles out on Whitfield Rd
(Address)
(2) Location: 1/4, 1/4, Sec 25 T5 R2
_____ miles _____ of _____
(distance) (direction) (Nearest Town)
(3) Topography: X
(Hilly) (Flat) (Level)
(4) Purpose of Well: Home
(Domestic, Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Brown Clay	0	22
Clay & red sand		32
Brown Clay		52
Blue clay		277
Shale		525
Clay & sandy shell		535
Shale		555
Clay & shells shell		575
Shale & shells & red sand		595
Shale		634
Shale & shells rock		644
Shale & shells & red sand		674
Shale		684
Shale & red sand		724
Fine sand & shale		754
Fine sand		784
Fine sand		808


Information upon completion of well:

(1) Diameter 2 inches.
(2) Total Depth 808 feet.
(3) Water Level 169 feet below top of ground.
(4) Cased to 790, Size 2"
(5) Screen: Size 2", Length 18 ft
(6) Were any formations sealed against pollution?
_____ yes, X no.

If YES depth of formation _____
Why _____

Drillers Remarks: _____

CODED



(Use Back Side)

Well No.

