

Rankin
M 20
8-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

CODED

WATER WELL DRILLERS LOG

Date: Aug. 22, 1966, Driller: W.G. Butler County RANKIN
(When well drilled) (Name) (Where well is located)

(1) Owner of Land: Bertha Lock
(Name)
Brandon, Miss.
RT -
(Address)
(2) Location: NE 1/4, NE 1/4, Sec. 33-T5R14
8 miles W. of Brandon
(distance) (direction) (Nearest Town)
(3) Topography: (Hilly) (Flat) (Level)
(4) Purpose of Well: Domestic
(Domestic Irrigation, Municipal, Industrial, Other)


Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Chalk	1-	10
Rock + sand	10-	20
Rock	20-	30
Rock + chalk	30-	80
Chalk	80-	90
Chalk + Shell	90-	120
Chalk	120-	122
Rock	122-	134
Rock + Shell	140-	150
Chalk	150-	160
Chalk shell + sand	160-	170
lignite + shell	170-	180
Chalk	180-	190
Chalk + lignite	190-	243
sand + chalk	243-	264
sand	264-	274
Chalk	274-	295

Information upon completion of well:

(1) Diameter 2 inches.
(2) Total Depth 295 feet.
(3) Water Level 148 feet below top of ground.
(4) Cased to 264, Size 2"
(5) Screen: Size 2", Length 13'
(6) Were any formations sealed against pollution?
no yes, NO no.

CODED

YES depth of formation _____
Why _____
Drillers Remarks: _____
Yield in gpm: 4
Size pump: 3/4 HP - Red Pump
Type power: Electric



[The page contains extremely faint and illegible text, likely bleed-through from the reverse side of the document. No specific words or phrases can be discerned.]