

N34

10-24-63

WATER WELL DRILLERS LOG

**CODED**

Date: 10/24, 1963, Driller: Frank Dwyer Sevier County Scott  
 (Name)


- (1) Owner of Land: Jul Moore  
 (Name)  
Delatchie, Miss.  
 (Address)
- (2) Location: 1/4, 1/4, Sec 17 55 T R  
3 miles South of Delatchie  
 (distance) (direction) (Nearest Town)
- (3) Topography: X  
 (Hilly) (Flat) (Level)
- (4) Purpose of Well: Chicken  
 (Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Brown Clay</u>	<u>0</u>	<u>22</u>
<u>Clay + Red Sand</u>		<u>32</u>
<u>Blue Clay</u>		<u>52</u>
<u>Clay + Sh. Grey Sand</u>		<u>62</u>
<u>Blue Clay</u>		<u>130</u>
<u>Rock</u>		<u>132</u>
<u>Blue Clay</u>		<u>325</u>
<u>Shale</u>		<u>360</u>
<u>Shale + Sh. lime Rock</u>		<u>370</u>
<u>Shale</u>		<u>410</u>
<u>Shale + Sh. lime Rock</u>		<u>420</u>
<u>Sandy Shell</u>		<u>440</u>
<u>Shale</u>		<u>470</u>
<u>Shale + Sh. fine Sand</u>		<u>490</u>
<u>Fine Sand + Sh. Clay</u>		<u>500</u>
<u>Shale</u>		<u>532</u>
<u>Fine Sand</u>		<u>540</u>
<u>Silt Sand</u>		<u>560</u>
<u>Shale + Sh. fine Sand</u>		<u>574</u>
<u>Fine Sand</u>		<u>584</u>
<u>Soft Shale</u>		<u>604</u>
<u>Shale</u>		<u>624</u>
<u>Fine Sand</u>		<u>686</u>

Information upon completion of well:

- (1) Diameter 2 inches.
- (2) Total Depth 686 feet.
- (3) Water Level 179 feet below top of ground.
- (4) Cased to 670', Size 2"
- (5) Screen: Size 2", Length 16 ft.
- (6) Were any formations sealed against pollution?  
 \_\_\_\_\_ yes, X no.

If YES depth of formation \_\_\_\_\_  
 Why \_\_\_\_\_  
 Drillers Remarks: \_\_\_\_\_



(Use Back Side)

Well No.

