

MISSISSIPPI BOARD OF WATER COMMISSIONERS

E100
200

RANKIN

P39 WATER WELL DRILLERS LOG

4-11-64

No Log MG5: 3

CODED Rankin

Date: 4-11-1964, Driller: JAMES M. NEE County: Rankin

(Name)

(1) Owner of Land: Smith - Vick
(Name)
JACKSON
(Address)

(2) Location: 1/4, 1/4, Sec 29 4^N E
1 miles East, of FLORENCE
(distance) (direction) (Nearest Town)

(3) Topography: _____
(Hilly) (Flat) (Level)

(4) Purpose of Well: Subdivision
(Domestic Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
SURFACE SOIL	10	10
SAND	25	35
Blue shale	75	110
SAND sh STKS	10	120
SAND shells shale	26	146
lime	29	175
Grey sdy sh	39	214
Grey sh-lignite	42	256
Grey sh	486	742
Grey sdy sh	97	839
Grey sh	61	900
ROCK	1	901
SAND-sh-STKS	40	941
SAND	54	995
Grey sh	8	1003
SAND	12	1015
SAND sh STKS	28	1043
Grey sh	20	1063
16 1/2 4"	336	
4" x 2 1/2" sweeper-celk-	3	
	339	
27 1/2 2 1/2	565	
	904	
1-10' 2 1/2 sss	10	
	914	
3 1/2 2 1/2	46	
	960	
2-10' 2 1/2 007-sss	20	
	980	
1-2 1/2" Test pipe		
& B P L	10	
	990	

Information upon completion of well:

(1) Diameter 4" x 2 1/2" inches.

(2) Total Depth 1063' feet.

(3) Water Level 165 feet below top of ground.

(4) Cased to 904, Size 4" x 2 1/2"


(5) Screen: Size 2 1/2" 008, Length 30'

(6) Were any formations sealed against pollution?
_____ yes, no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____



CODED (Use Back Side)

Well No.

