

P55  
3-66

WATER WELL DRILLERS LOG

**CODED**

Date: 3/24, 1966, Driller: HALL DRILLING Co County HANTS  
(Name)

- (1) Owner of Land: CRYSTAL WATER  
BROADUS, S. COMPERE  
(Address) s.w. 4
- (2) Location: SE 1/4, NW 1/4, Sec. 18 T42R2E  
2 miles NORTH, of FLORANCE,  
(distance) (direction) (Nearest Town)
- (3) Topography: FLAT  
(Hilly) (Flat) (Level)
- (4) Purpose of Well: MUNICIPAL  
(Domestic Irrigation  
Municipal, Industrial, Other)


Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
SURFACE SOIL	6	6
GREY MARL	18	24
BROWN MARL	57	75
ROCK LEDGES	30	105
SAND-SEA SHELL	8	113
SAND + SHALE	35	148
HARD SHALE	43	191
SHALE & FINE SAND	2.1	212
YAZOO CLAY	409	621
MOODY BRANCH	15	636
FINE SAND + SHALE	92	728
SAND SHALE & LIG	114	842
SAND HARD-CLAY	50	892

Information upon completion of well:

- (1) Diameter 6 X 4 inches.
- (2) Total Depth 892 feet.
- (3) Water Level 185 feet below top of ground.
- (4) Cased to 400', Size 6  
442-4"
- (5) Screen: Size 4, Length 50.
- (6) Were the formations sealed against pollution?  
\_\_\_\_\_ yes, X no.

If YES depth of formation \_\_\_\_\_  
Why \_\_\_\_\_

Drillers Remarks: TOP 100'  
CEMENTED



26 Well No.

(Use Back Side)

(X)