

Rankin

P57

MISSISSIPPI BOARD OF WATER COMMISSIONERS

6-66

Electrical Log by M.G.S., 1966

WATER WELL DRILLERS LOG

**CODED**

Date: 6-9-, 1966, Driller: James M. N... County RANKIN

(Name)

(1) Owner of Land: Ebenezer Methodist Church  
(Name)

JACKSON MISS  
(Address)

(2) Location: S.E. 1/4 NE 1/4, Sec. 6 T. 2 R. 2  
RANKIN CO  
5 miles S.E. of JACKSON  
(distance) (direction) (Nearest Town)

(3) Topography:  (Hilly)  (Flat)  (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Gravel, Clay, Shell, etc.	Thick- ness Feet	Depth Feet
SURFACE SOIL	5	5
Clay	5	10
SAND	10	20
Grey shale	478	498
Grey sdy sh	13	511
Grey shale	71	582
Grey sh sand strcs	10	592
LIGNITE	20	612
Grey sh sand strcs	48	660
ROCK	1	661
SAND	9	670
Grey sh	4	674
SAND	5	679
SAND & sh	6	685
SAND	55	740
Grey sh	2	742
SAND	10	752
Grey sh	20	772
34 Jts 2"	714	
2-10' 2" 008 SSS	20	
	734	
1-Jt 2" 0 BPV	12	
	746	

Information upon completion of well:

(1) Diameter 2" inches.

(2) Total Depth 772 feet.

(3) Water Level 170 feet below top of ground.

(4) Cased to 714', Size 2"

(5) Screen: Size 2" 008, Length 20'


(6) Were any formations sealed against pollution?  
 yes,  no.

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: White water

**CODED**



(Use Back Side)

Well No.

20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100

11