

RANKIN
Q 20

ELECT LOG - MISS G Survey
WATER WELL DRILLERS LOG

CODED

Date: 9-26, 1964, Driller: Lones McNEE (Name)


- (1) Owner of Land: Dewey Myers
(Name)
Brendon Miss
(Address)
- (2) Location: NE 1/4, SW 1/4, Sec. 20 T4 R3
7 miles SW of Brendon
(distance) (direction) (Nearest Town)
- (3) Topography: (Hilly) (Flat) (Level)
- (4) Purpose of Well: Domestic
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Surface soil	10	10
Sand	25	35
Blue shale	45	80
Grey shale	40	120
Grey sh fossils	61	181
Rock sh strata	31	212
Grey sdy sh	38	250
Sand	12	262
Grey sdy sh	21	283
Sand	5	288
Grey sdy sh	8	296
Grey sh	39	335
10ths - 2"	20	
2 - 1/4	44	
1/4 screen	11	
	261	

Information upon completion of well:

- (1) Diameter 2 inches.
- (2) Total Depth 335 feet.
- (3) Water Level 74 feet below top of ground.
- (4) Cased to 250', Size 2" x 1/4"
- (5) Screen: Size 1/4", Length 11
- (6) Were any formations sealed against pollution?
_____ yes, no.

CODED



If YES depth of formation _____

Why _____

Drillers Remarks: _____

(Use Back Side)

Well No. 11

