

Rankin
T 10
7-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

Electrical Log by M.G.S.
WATER WELL DRILLERS LOG

CODED

Date: 7-25, 1966, Driller: James McNeas County: Rankin

(Name)

(1) Owner of Land: E. B. Morrison
(Name)
Florence Miss
(Address)
N.W. 1/4
(2) Location: SW 1/4, SE 1/4, Sec. 5 3 N E
7 miles West of Florence
(distance) (direction) (Nearest Town)
(3) Topography: Level
(Hilly) (Flat) (Level)
(4) Purpose of Well: Domestic
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>Surface soil</u>	<u>10</u>	<u>10</u>
<u>Clay sand</u>	<u>19</u>	<u>23</u>
<u>Blue shale</u>	<u>57</u>	<u>80</u>
<u>sand</u>	<u>13</u>	<u>93</u>
<u>Blue shale</u>	<u>67</u>	<u>160</u>
<u>Lime sh str</u>	<u>23</u>	<u>183</u>
<u>LIME sd str</u>	<u>10</u>	<u>193</u>
<u>sand</u>	<u>5</u>	<u>198</u>
<u>sand-sh</u>	<u>19</u>	<u>226</u>
<u>sand</u>	<u>3</u>	<u>229</u>
<u>Grey sh</u>	<u>12</u>	<u>241</u>
<u>sand</u>	<u>9</u>	<u>250</u>
<u>Grey sh lignite</u>	<u>18</u>	<u>268</u>
<u>Grey sh</u>	<u>81</u>	<u>349</u>


Information upon completion of well:

(1) Diameter 2 inches.
(2) Total Depth 349 feet.
(3) Water Level 47 feet below top of ground.
(4) Cased to 172, Size 2
(5) Screen: Size 1 1/4 .90 mesh, Length 40
(6) Were any formations sealed against pollution?
no

CODED

<u>9 fts 2"</u>	<u>6</u>
<u>1 xx heavy NIP</u>	<u>6"</u>
<u>40' 1/4 90 mesh</u>	<u>172</u>
<u>screen with</u>	
<u>RIGHT HAND LEAD</u>	
<u>seal</u>	<u>40</u>
	<u>212</u>

If YES depth of formation _____
Why _____
Drillers Remarks: Water white



(Use Back Side)

Well No.

