

U23

GW-1718

WATER WELL DRILLERS LOG

6-66

75  
CODED

Date: JUNE 1, 1966, Driller: HALL DRILLING CO County: HALLS

(Name) RANKIN

(1) Owner of Land: STAR WATER CO

(Name)

STAR MISS

(Address)

(2) Location: SE 1/4, NE 1/4, Sec. 24 T. 3 R. 2 E

X miles X of STAR,  
(distance) (direction) (Nearest Town)

(3) Topography: HILLY

(Hilly) (Flat) (Level)

(4) Purpose of Well: MUNICIPAL

(Domestic Irrigation, Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter 6 X 4 inches.

(2) Total Depth 690 feet.

(3) Water Level 240 feet below top of ground.

(4) Cased to 690, Size 400'-6"  
260'-4"

(5) Screen: Size 4", Length 30'

(6) Were any formations sealed against pollution?

yes,  no.

If YES depth of formation

Why


Drillers Remarks:

CASING CEMENTED

400' FROM TOP OF

GROUND

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>SURFACE SOIL</u>	<u>1</u>	<u>1</u>
<u>RED SAND</u>	<u>19</u>	<u>20</u>
<u>GRAVEL + RED SAND</u>	<u>22</u>	<u>42</u>
<u>YELLOW CLAY + ROCK</u>	<u>22</u>	<u>64</u>
<u>ROCK + SHALE</u>	<u>16</u>	<u>80</u>
<u>GREY SHALE</u>	<u>60</u>	<u>140</u>
<u>COURSE WHITE SAND</u>	<u>-</u>	<u>-</u>
<u>W/SHALE STREAKS</u>	<u>65</u>	<u>205</u>
<u>ROCK + SHALE</u>	<u>22</u>	<u>227</u>
<u>SHALE</u>	<u>41</u>	<u>268</u>
<u>SAND + SHALE</u>	<u>107</u>	<u>375</u>
<u>SHALE + ROCK</u>	<u>84</u>	<u>459</u>
<u>ROCK LEDGES</u>	<u>61</u>	<u>520</u>
<u>SAND SEA SHELL</u>	<u>20</u>	<u>540</u>
<u>SAND + SHALE</u>	<u>25</u>	<u>565</u>
<u>HARD SHALE</u>	<u>11</u>	<u>576</u>
<u>SAND + SHALE</u>	<u>3.2</u>	<u>608</u>
<u>COURSE SAND W/</u>	<u>-</u>	<u>-</u>
<u>SHALE STREAKS</u>	<u>82</u>	<u>690</u>



Well No.

(Use Back Side)

(X)