

SCOTT MISSISSIPPI BOARD OF WATER COMMISSIONERS

K 4
10-10-60

WATER WELL DRILLERS LOG

K 302
3

Date: 10/10, 19 60, Driller: James McGee County Scott

(Name)

(1) Owner of Land: J. B. Black
(Name)

Forest, Miss.
(Address)

(2) Location: 1/4, 1/4, Sec. 19 T. R.

9 miles West, of Forest
(distance) (direction) (Nearest Town)

(3) Topography: X
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
(Domestic Irrigation
Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 682 feet.

(3) Water Level 225 feet below top of ground.

(4) Cased to 672', Size 2"


(5) Screen: Size 2", Length 10'

(6) Were any formations sealed against pollution?
yes, X no.

If YES depth of formation

Why

Drillers Remarks: Good



Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay.	0	22
Clay & stks. sand.	22	42
Fine sand & Stks. clay	42	52
Fine sand.	52	72
Fine Sand & clay.	72	82
Blue clay & sand.	82	122
Clay & stks. rock.	122	132
Blue clay.	132	171
Clay & stks. rock.	171	182
Blue clay.	182	292
Shale.	292	382
Shale & stks. rock.	382	402
Shale.	402	432
Shale & stks. rock.	432	442
Shell.	442	448
Rock.	448	452
Shell.	452	462
Shale.	462	472
Shale & rock.	472	482
Mucky sand.	482	492
Soft shale.	492	502
Shale & fine sand.	502	552
Fine sand.	552	562
Fine sand & clay.	562	572
Fine sand.	572	592
Mucky sand.	592	602
Fine sand.	602	612
Clay.	612	619
Fine sand.	619	622
Clay.	622	629
Sand. (Screen Set)	629	682

(Use Back Side)

Well No.

