

SHARKEY MISSISSIPPI BOARD OF WATER COMMISSIONERS

A40  
9-4-57

WATER WELL DRILLERS LOG

CO/1/65  
**CODED**

Date: Sept. 4, 1957, Driller: Layne-Central Company County Sharkey  
(Name)

(1) Owner of Land: R. W. Williams  
(Name)  
Delty City, Mississippi  
(Address)

(2) Location: 22  $\frac{1}{4}$ , 23  $\frac{1}{4}$ , Sec. 23 T14R6,  
2 miles south, of Delta City,  
(distance) (direction) (Nearest Town)

(3) Topography: flat  
(Hilly) (Flat) (Level)

(4) Purpose of Well: irrigation  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay	37	37
Fine sand	9	46
Coarse sand	6	52
Coarse sand, clay balls & lignite	10	62
Coarse sand, pea rock & clay balls	10	72
Sand & gravel	10	82
Sand & gravel	20	102
Sand & big gravel	14	116

Information upon completion of well:

(1) Diameter 18x16 inches.

(2) Total Depth 116 feet.

(3) Water Level 12' 6" feet below top of ground.

(4) Cased to 66' Size 18"  
2' of 18" x 16" swage

(5) Screen: Size 16", Length 50'


(6) Were any formations sealed against pollution?  
no yes, no no.

**CODED**

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks:  
2800 GPM.  
Engine drive.



Well No.

