

WATER WELL DRILLERS LOG

April 14 19 81
date well completed

Dickling & Assoc.
firm name

Sharkey
county well located

LANDOWNER: Donald Ourst

P.O. Box 247

Delta City, MS 39061
(mailing address)

WELL LOCATION:

sec. 26 T 14 (N) R 6 E
S W
4 miles (distance) (direction) of Nitta Yuma (nearest town)

WELL PURPOSE: Irrig
(home, irrigation, municipal, industrial)


WELL COMPLETION DATA:

- (1) diameter (inches) 16"
- (2) total depth (feet) 104'
- (3) static water level (feet) 16' below top of ground.
- (4) casing Steel, 20' (material), (depth)
If telescope see back.
- (5) screen 20' length, 84' (depth to top)
16" (size), STEEL (material)
- (6) pump 60 (HP), 3800 (yield gpm)
Propane (type power)
- (7) electric log NO (yes or no)
NO (organization running log)
- (8) how well bottom plugged STEEL plug

description of formations encountered

from to

TOP SOIL	0	5
CLAY	5	10
BROWN CLAY	10	15
BROWN CLAY FINES.	15	20
FINE SAND	20	25
FINE SAND	25	30
FINE + MED SAND	30	35
COURSE SAND + GRAVEL	35	40
FINE SAND + CLAY	40	45
Lignite COAL	45	50
COURSE SAND + GRAVEL	50	55
COURSE SAND	55	60
COURSE SAND	60	65
COURSE SAND + GRAVEL	65	70
"	"	70 75
"	"	75 80
"	"	80 85
"	"	85 90
COURSE SAND	90	95
COURSE SAND SM. GRAVEL	95	100
Bottom at 104'	100	104



DRILLERS REMARKS:

sketch and show depths.

GROUND LEVEL

SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.