

MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES

Bureau of Land and Water Resources

Southport Mall

P.O. Box 10631

Jackson, Mississippi 39209

WATER WELL DRILLERS LOG

A 46 72
 Sharkey
 CL 2434
 5-9-83

5-9 1983 LAYNE CENTRAL CO. SHARKEY
 date well completed firm name county well located

LANDOWNER:
 Caney Bayou Farms
 Delta City, MS
 (mailing address)

description of formations encountered	from	to
clay	0	16
sand	16	30
c. sand/pea gravel	30	60
gravel sand	60	123

WELL LOCATION:
 sec. 26 T 14 N R 6 E
 3 miles S Delta City
 (distance) (direction) (nearest town)

WELL PURPOSE: irrigation
 (home, irrigation, municipal, industrial)

WELL COMPLETION DATA:
 (1) diameter (inches) 32"
 (2) total depth (feet) 123'
 (3) static water level (feet) 9' below above top of ground.
 (4) casing steel 73'
 (material) (depth)
 16" if telescope see back.
 (size)
 (5) screen 50' 73'
 (length) (depth to top)
 16" st. steel
 (size) (material)
 (6) pump 60 2500
 (HP) (yield gpm)
 Diesel
 (type power)
 (7) electric log no
 (yes or no)
 (organization running log)
 (8) how well bottom plugged st. plate

DRILLERS REMARKS:

CODED


DEPT. OF NATURAL RESOURCES
 BUREAU OF LAND & WATER RESOURCES

OCT 10 1983

RECEIVED

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.